

Notes:

1. ALL DIMENSIONS ARE IN mm COORDINATES AND ELEVATIONS ARE IN m UNLESS OTHERWISE INDICATED.
2. GRATING SPECIFICATION:
   - S235JR OR HIGHER STRENGTH STEEL HOT DIP GALVANIZED 30 mm THICKNESS GRATING PANELS.
   - 1 x 2 m MAXIMUM APPROX. PANEL SIZE.
   - 30 x 23 MESH (34 mm BETWEEN BEARING BARS AND 23 mm BETWEEN LINKING RODS ACC. WITH ISO 14122 NOT ALLOWING A 20 mm DIAMETER PASSING THROUGH)
   - 30x3 BEARING BAR SECTION AND ø6 mm LINKING TWISTED ROD
   - 200 mm TYPICAL MAXIMUM SPAN FOR 5 KN/m^2 ALLOWABLE LOAD.
   - ALL STAIR STEPS TO HAVE ANTISLIP EDGE.
   - ALL PANELS EDGES FACING VOIDS FOR EQUIPMENT OR PIPING WITHOUT HANDRAIL KICKPLATE WILL INCLUDE A BUILT-IN WELDED AND GALVANIZED EQUIVALENT KICKPLATE.
3. CONSTRUCTOR SHOULD CHECK ALL DIMENSIONS BEFORE FABRICATION AND CONSTRUCTION. ALSO ALL PIPING AND CABLE TRAY SUPPORTS AND PIPE CROSSING NOT SHOWN MUST BE CONSIDERED PRIOR FABRICATION. ANY REPAIR OR MODIFICATION MUST BE PROPERLY FIXED AND GALVANIZATION RESTORED.
4. GRATING CONNECTION TO THE STRUCTURES TO BE DONE WITH ADEQUATE VENDOR REMOVABLE CLAMPS.

Rev.	Author/Date		Checked/Date		Approved/Date		Description
0	PCR	28/10/2022	ATB	28/10/2022	ATB	28/10/2022	FOR CONSTRUCTION

Custumer:
JSC RMG Auramine LLC

Project: BEQTAQARI DETAIL ENGINEERING

Title:
GRINDING PLANT
GRATING PANELS DETAIL
T.O.S. +718.970

3d model:

Customer doc. code:

Area:	Scale:	Format:	Doc. code:	Rev:
200	1:25	A1	P1384-200-ST-009	0