



① DEMOLITION PLAN - SECOND FLOOR #207-AR-003  
1/100



② NEW CONSTRUCTION PLAN -SECOND FLOOR #207-AR-003  
1/100

1. Demolition of grid suspended ceiling- total 7.1m<sup>2</sup>
2. Demolition of equipment on the ceiling -30\*50(2m) duct  
-30\*30(2m) duct
3. Demolition of plasterboard walls in front of the shafts.(2X113\*267cm)
4. Closing the hole in front of the shaft by bims wall 2X (125\*400cm)
5. Construction of new EI120 shaft walls-2\*25mm manufactured from one side-(2X113\*267cm)
6. Demolition of existing door in the corridor (120\*210cm)
7. Demolition of plasterboard walls which separates the corridor (216\*267cm)
8. Construction of new EI60 compartment wall-2\*12.5mm manufactured from both sides, see wall detail. (216\*267cm)
9. Provide a new double-leaf, EI45 fire door (120\*210cm) to the compartment wall.
10. Mounting new grid suspended ceiling- total 7.1m<sup>2</sup>
11. Reassembling of equipment on the ceiling -30\*50(2m) duct  
-30\*30(2m) duct
12. Install fire dampers on ducts (2m)
13. Firestopping around the cavities of the ducts.
14. Repairing of vinyl tiling on the floor of the parts which are damaged while demolishing the walls.

LEGEND AND MATERIAL LIST	
SYMBOL	DESCRIPTION
	TO BE DEMOLISHED 60*60 GRID SUSPENDED CEILING
	TO BE MOUNTED 60*60 GRID SUSPENDED CEILING
	TO BE DEMOLISHED PVC HYGIENIC SUSPENDED CEILING
	TO BE MOUNTED PVC HYGIENIC SUSPENDED CEILING
	TO BE DEMOLISHED PLASTERBOARD SUSPENDED CEILING
	TO BE MOUNTED PLASTERBOARD SUSPENDED CEILING
	TO BE CLOSED HOLE BY BIMS WALL
	TO BE DEMOLISHED EXISTING PLASTERBOARD WALL
	TO BE DEMOLISHED EXISTING CERAMIC TILE
	TO BE CONSTRUCTED PLASTERBOARD WALL WITHOUT FIRE RATING
	TO BE CONSTRUCTED CERAMIC TILE
	TO BE CONSTRUCTED COMPARTMENT WALL FOR FIRE SEPARATION EI60 - 2x12,5 mm /from both sides
	TO BE CONSTRUCTED SHAFT WALL FOR FIRE SEPARATION EI120 - Shaft Wall 2x25 mm Flameboard /from one side
	TO BE CONSTRUCTED WALL FOR FIRE SEPARATION EI120 - 2x15 mm /from both sides
	TO BE CONSTRUCTED WALL FOR FIRE SEPARATION EI60 - 2x15 mm Plasterboard /from one side
	TO BE CONSTRUCTED HALL WALL FOR FIRE SEPARATION EI60 - One Layer
	TO BE DEMOLISHED EXISTING DOOR
	TO BE MOUNTED NEW FIRE DOOR
	TO BE REMOUNTED EXISTING DOOR



(Existing view towards the compartment no.105)



(Existing view towards the compartment no.107)




(Existing duct)




(Existing duct and cavities around it)

③ PHOTOGRAPHS OF CURRENT SITUATION - SECOND FLOOR #207-AR-003



④ SHAFT WALL DETAIL FOR FIRE SEPARATION EI120 /from one side



⑤ COMPARTMENT WALL DETAIL FOR FIRE SEPARATION EI60 /from both sides

KEY PLAN		
<input checked="" type="checkbox"/> FOR SYSTEM APPROVAL <input type="checkbox"/> FOR TENDER <input type="checkbox"/> FOR INSTALLATION <input type="checkbox"/> AS BUILT		
For System Approval		
Date	Explanation	
CLIENT 		
DESIGNER TASARIM, DANIŞMANLIK VE EĞİTİM HİZMETLERİ LTD.ŞTİ. Cetin EMEC Bulvarı 2. Cad. No : 37/4 A. ÖVEÇLER - 06460 ANKARA / TURKEY Tel : +90-312-472 62 88 Faks : +90-312-472 62 89 e-posta: info@karina.gen.tr		
TECH. CONSULTANCY : KARİNA	FIRE & LIFE SAFETY IMPROVEMENT OF FIRE & SMOKE COMPARTMENT FEATURES DRAWINGS	
SYSTEM DESIGN : KARİNA		
MATERIAL SUPPLY : -		
INSTALLATION : -		
APPROVAL : -	DRAWING NO : EVEX-SNS-KAR-207-AR-003	REV. 00
DATE : 08.11.2020		* / *
SCALE : 1/100	FILE NAME : C:\EVEX-SNS-KAR-204-205-206-207.*	