



② NEW CONSTRUCTION PLAN - FIFTH FLOOR #502-AR-001  
1/100

- PART I**
1. Demolition of equipment on the ceiling of the elevator hall  
-3 60x60cm led lighting fixture  
-1 smoke detector  
-1 diffuser with plenum box  
-1 diffuser without plenum box  
-1 camera  
-1 fan coil(4m)  
-0 300 flexible duct
  2. Demolition of grid suspended ceiling in the elevator hall-- total 22.8m2
  3. Demolition of the equipment on the walls of the elevator hall  
-3 elevator control panel  
-1 fire button  
-1 audio-visual device  
-card reader  
-1 thermostat  
-1 door opener button
  4. There already exists one layer of plasterboard, but it does not continue up to the ceiling, the height of the floor is so high, so 40cm height must be removed between the existing plasterboard wall and suspended ceiling will be replaced by mounting one layer of 12.5mm plasterboard.  
(195x40cm,60x40cm,67x40cm,60x40cm,27x40cm,150x40cm,84x40cm,184x40cm,27x40cm,110x40cm,28x40cm,100x40cm,28x40cm,114x40cm,310x40cm,200x40cm,43x40cm,27x40cm,19x40cm,150x40cm,34x40cm,50x40cm,28x40cm,120x40cm,194x40cm,165x40cm)
  5. Demolition of the existing doors of fire staircase and the elevator hall (2x150x210cm)
  6. Demolition of the existing door of holding room which opens to the fire staircase. (80x210cm)
  7. For holding room, provide a new E90 door to the wall which is adjacent to the elevator hall and can be entered from the elevator hall. (80x210cm)
  8. Provide a new double-leaf E90 door to the elevator hall entrance (150x210cm)  
(one double-leaf E90 door for fire staircase (one leaf is 20cm, one leaf 155cm, height is 210cm))
  9. One layer of 25mm plasterboard will be mounted over the existing plasterboard walls from the hall side.  
(195x300cm,60x300cm,67x300cm,60x300cm,27x300cm,150x300cm,84x300cm,184x300cm,27x300cm,110x90cm,28x100x300cm,28x300cm,114x90cm,310x300cm,200x300cm,43x300cm,27x300cm,19x300cm,150x300cm,34x300cm,50x120x300cm,120x90cm,194x300cm,165x300cm)
  11. Fill the space above the door with mortar (380x360cm)
  12. Mounting of E1120 grid suspended ceiling to the elevator hall-- total 22.8m2
  13. Reassemble the demolished equipment on the ceiling
- PART II**
14. Demolition of the plasterboard wall at the staircase part(175x245cm,48x245cm,80x35cm)
  15. Close the space of the demolished door by bins wall (80x210cm)
  16. Construct E1200 wall by mounting of two layers of 25mm plasterboards from the inside of the fire staircase (175x245cm,48x245cm,80x35cm)


		<input type="checkbox"/> FOR SYSTEM APPROVAL <input type="checkbox"/> FOR TENDER <input type="checkbox"/> FOR INSTALLATION <input type="checkbox"/> AS BUILT
<p>KEY PLAN</p>		
	For System Approval	
Date	Explanation	
CLIENT <div style="float: right; text-align: right;">           EVEX GEORGIA HEALTHCARE GROUP            40 Waltham Parkway Ave            Niles - 62564            Tel: +995 322 55 05 05         </div>		



④ WALL DETAIL FOR FIRE SEPARATION EI120/ from one side



⑥ SUSPENDED CEILING DETAIL FOR FIRE SEPARATION E1120



⑤ WALL DETAIL FOR FIRE SEPARATION EI120/over the existing plasterboard

